"C3045 Expo Valley Views"

PROJECT DATA SHEET

مـدينة إكـسبو دبـي
EXPO CITY DUBAI

GENERAL INFORMATION

PROJECT DATA

Date:	10/06/2026
Document Revision No.:	3



Project ID:	C3045
Project Name:	EXPO VALLEY VIEWS
Plot No. :	5210986
Bldg. Height-DMD Level (M):	97.75 m
Bldg. Height-Design Level (M):	97.00 m
Project Description:	8 residential buildings on partial podium area and one basement floor with 2000 sq.m. retail area including 804 units.
Building Area Coverage Percentage:	
Affection Plan Restrictions: (e.g. Setbacks, Parking, Building Height)	Max. GFA 110000 sq.m. Max. allowed height 97 m from DMD level (97.7 m as per DCAA NOC)

Building Usage:	Residential	Mixed-Use	Commercial	Hotel	Others

Project Phase:	Stage 1 (Initiation)	Stage 2 (Concept)	Stage 3 (Development)	Stage 4 (Technical)	Stage 5 (Construction)

ASSETS MATRIX

UNIT TYPE SUMMARY

	ITEM	NO.	%	INCL. BALCONY SQ.M.	INCL. BALCONY SQ.FT.	EXCL. BALCONY SQ.M.	EXCL. BALCONY SQ.FT.
	Residential Units:						
1	1 Bedroom	227	28.23%	83.07	894.16	71.48	769.40
2	2 Bedroom	422	52.49%	157.97	1,700.42	135.12	1,454.37
3	3 Bedroom	155	19.28%	150.78	1,622.98	128.04	1,378.21
4	4 Bedroom	0	0	-	-	-	-
5	5 Bedroom	0	0	-	-	-	-
	TOTAL	**804**	**100%**	**391.82**	**4,217.56**	**334.64**	**3,601.98**
	Retail Units:	5			-	1,129.00	12,152.44
	F&B Units:	5			-	871.00	9,375.36
	TOTAL	**10**	**0%**	**-**	**-**	**2,000.00**	**21,527.80**

RESIDENTIAL UNIT BREAKDOWN

	ITEM	NO.	%	INCL. BALCONY SQ.M.	INCL. BALCONY SQ.FT.	EXCL. BALCONY SQ.M.	EXCL. BALCONY SQ.FT.
1	1BD	227	28.2%	83.08	894.26	71.48	769.44
2	2BR-Type 1 (Rectangular)	84	10.4%	126.91	1,366.05	107.81	1,160.46
3	2BR-Type 1A (Rectangular)	80	10.0%	124.38	1,338.81	107.78	1,160.13
4	2BR-Type 2 (Square)	81	10.1%	137.24	1,477.24	116.64	1,255.50
5	2BR-Type 3 (L Shaped)	84	10.4%	137.00	1,474.65	116.40	1,252.92
6	2BR-Type 4 (Corner)	81	10.1%	126.12	1,357.59	107.02	1,152.00
7	2BR-Type 5 (Tower 07)	12	1.5%	137.24	1,477.24	116.64	1,255.50
8	3BR-Type1 (Side)	95	11.8%	169.25	1,821.79	143.85	1,548.39
9	3BR-Type2 (Center)	57	7.1%	175.16	1,885.44	148.86	1,602.35
9	3BR-Type 2A (Center-First Floor)	3	0.4%	177.54	1,911.04	151.24	1,627.95
	TOTAL	**804**	**100.0%**	**1,393.93**	**15,004.11**	**1,187.73**	**12,784.63**

AREA STATEMENT SUMMARY

AREA STATEMENT SUMMARY

ITEM	SQ.M.	SQ.FT.
Plot Area:	39,681.19	427,124.36
FAR Allowed:	2.77	-
FAR Proposed:	-	-
GFA Allowed:	110,000.00	1,184,029.00
GFA Proposed:	105,175.30	1,132,096.41
Residential:	103,175.30	1,110,568.61
Retail:	2,000.00	21,527.80
BUA Proposed:	173,494.10	1,867,473.14
Podium:	37,809.20	406,974.45
Towers:	135,684.90	1,460,498.70
NSA Proposed:	103,027.10	1,108,973.40
Residential:	101,027.10	1,087,445.60
Retail:	2,000.00	21,527.80

BUILT-UP AREA BREAKDOWN (Per Level)

	ITEM	SQ.M.	SQ.FT.
1	Basement 1	32,031.40	344,782.79
2	Ground Floor	18,022.20	193,989.16
3	1st Floor	11,774.20	126,736.31
4	2nd Floor	12,177.29	131,075.13
5	3rd Floor	12,177.29	131,075.13
6	4th Floor	12,177.29	131,075.13
7	5th Floor	11,811.89	127,142.00
8	6th Floor	10,729.29	115,489.00
9	7th Floor	10,385.09	111,784.07
10	8th Floor	10,106.77	108,788.26
11	9th Floor	8,938.94	96,217.90
12	10th Floor	7,147.88	76,939.09
13	11th Floor	7,080.68	76,215.75
14	12th Floor	4,054.18	43,638.81
15	13th Floor	3,537.30	38,075.14
16	14th Floor	1,290.70	13,892.97
17	Roof	51.70	556.49
	TOTAL	**173,494.10**	**1,867,473.14**

PARKING/GARBAGE/LIFT SUMMARY

PARKING CALCULATION

ITEM	NO.	REQUIRED	PROPOSED
Units less than 150 sqm	801	801	803
Units more than 150 sqm	3	6	6
Tandem		152	151
Retail	10	29	29
Visitors		15	15
VAN PARKING		-	8
TOTAL		**1003**	**1012**
Bicycle Parking		353 RACKS	353 RACKS
Motorbikes Parking		5	5
POD Parking		21	22
EV Parking		22	22
Preferred Parking		63	64

Notes:-
EV, POD, Prefered Parking (Distributed proportionately near each building)
- 2% POD
- 2 % Electric Vehicles parking
- 7% preferred parking per asset (Hybrid/ Car share)

AREA EFFICIENCY

ITEM	%
GFA/BUA	60.62%
NSA/GFA	97.96%
NSA/BUA	59.38%

BUILT-UP AREA BREAKDOWN (Per Tower)

	ITEM	SQ.M.	SQ.FT.
1	Basement 1	32,031.43	344,783.11
2	Podium Landscape +Guard House	5,777.75	62,191.12
3	Tower - 1 2951-G+5	8,932.18	96,145.09
4	Tower - 2 2952-G+7	13,321.91	143,395.71
5	Tower - 3 2953-G+8	14,940.21	160,814.93
6	Tower - 4 2954-G+10	17,771.70	191,292.80
7	Tower -5 2955-G+13	22,235.75	239,343.39
8	Tower -6 2956-G+12	19,961.69	214,865.63
9	Tower -7 2957-G+12	21,215.84	228,365.18
10	Tower - 8 2958-G+10	17,305.64	186,276.18
	TOTAL	**173,494.10**	**1,867,473.14**

PARKING DISTRIBUTION

LEVEL	NO.	
Basement/Podium 2	na	
Basement/Podium 1	807	Including 129 slots for Tandem & 8 slots for Van parking
Ground Floor	205	Including 22 slots for Tandem
TOTAL	**1012**	

CONSULTANTS

NAME	CONTACT PERSON	EMAIL
DESIGN:		
Main Consultant	SSH	
Architect-of-Record	SSH	
Acoustic	Inhabit	
Civil Works		
Façade & BMU	Fencon	
Fire & Life Safety	Design Confidence	
Infrastructure	SSH	
Interior Design	SSH	
Landscape	SSH	
Lighting	LET	
MEP	SSH	
Security	SSH	
Signage & Wayfinding	The Design Company	
Structural	SSH	
Structural (3rd Party)		
Sustainability	Platinum	
Traffic Impact (TIS)	Al Turath	
Vertical Transportation	Dunbar & Boardman	
Others		
CONSTRUCTION:		
Supervision Consultant	SSH	
Main Contractor		

RETAIL UNIT BREAKDOWN

	ITEM	%	INCL. OUTDOOR SQ.M.	INCL. OUTDOOR SQ.FT.	EXCL. OUTDOOR SQ.M.	EXCL. OUTDOOR SQ.FT.
1	Retail 1	10.85%	217.00	2,335.77	217.00	2,335.77
2	F&B 1	9.20%	184.00	1,980.56	184.00	1,980.56
3	F&B 2	10.20%	204.00	2,195.84	204.00	2,195.84
4	Retail 2	16.95%	339.00	3,648.96	339.00	3,648.96
5	Retail 3	7.40%	148.00	1,593.06	148.00	1,593.06
6	Retail 4	10.75%	215.00	2,314.24	215.00	2,314.24
7	Retail 5	8.00%	160.00	1,722.22	160.00	1,722.22
8	F&B 3	10.15%	203.00	2,185.07	203.00	2,185.07
9	F&B 4	7.50%	150.00	1,614.59	150.00	1,614.59
10	F&B 5	6.50%	130.00	1,399.31	130.00	1,399.31
11	Retail visitor toilets	2.50%	50.00	538.20	50.00	538.20
	TOTAL	**100%**	**2,000.00**	**21,527.80**	**2,000.00**	**21,527.80**

AMENITIES AREA BREAKDOWN

	ITEM	%	INCL. OUTDOOR SQ.M.	INCL. OUTDOOR SQ.FT.	EXCL. OUTDOOR SQ.M.	EXCL. OUTDOOR SQ.FT.
1	Multipurpose Hall	16.26%	221.00	2,378.82	221.00	2,378.82
2	Indoor Games Room	5.12%	69.55	748.63	69.55	748.63
3	Kids Club, Play area & Toilets	27.80%	377.83	4,066.92	377.83	4,066.92
4	Main Gym	25.63%	348.39	3,750.04	348.39	3,750.04
5	Sattelite Gym 01	11.27%	153.19	1,648.92	153.19	1,648.92
6	Sattelite Gym 02	8.31%	112.88	1,215.03	112.88	1,215.03
7	Prayer Rooms	5.61%	76.25	820.75	76.25	820.75
	TOTAL	**100%**	**1,359.09**	**14,629.11**	**1,359.09**	**14,629.11**

LANDSCAPE AREA RATIO

ITEM	SQ.M.	%
Softscape	4846.89	25.49%
Hardscape	14171.38	74.51%
TOTAL	19,018.27	

GROSS FLOOR AREA BREAKDOWN

	ITEM	SQ.M.	SQ.FT.
1	Basement 1	80.70	868.65
2	Ground Floor	5,382.10	57,932.39
3	1st Floor	9,753.10	104,981.39
4	2nd Floor	9,873.51	106,277.45
5	3rd Floor	9,873.51	106,277.45
6	4th Floor	9,873.51	106,277.45
7	5th Floor	9,567.31	102,981.55
8	6th Floor	8,644.11	93,044.31
9	7th Floor	8,410.69	90,531.80
10	8th Floor	8,176.34	88,009.28
11	9th Floor	7,182.24	77,308.89
12	10th Floor	5,719.81	61,567.50
13	11th Floor	5,719.81	61,567.50
14	12th Floor	3,147.94	33,884.10
15	13th Floor	2,843.97	30,612.18
16	14th Floor	926.67	9,974.55
17	Roof	-	-
	TOTAL	**105,175.30**	**1,132,096.44**

NET SELLABLE AREA BREAKDOWN

	ITEM	SQ.M.	SQ.FT.
1	Basement 1	-	-
2	Ground Floor	1,883.72	20,276.17
3	1st Floor	10,310.40	110,980.11
4	2nd Floor	10,010.88	107,756.11
5	3rd Floor	10,010.88	107,756.11
6	4th Floor	10,010.88	107,756.11
7	5th Floor	9,663.88	104,020.98
8	6th Floor	8,764.48	94,339.93
9	7th Floor	8,507.85	91,577.59
10	8th Floor	8,251.13	88,814.32
11	9th Floor	7,262.28	78,170.43
12	10th Floor	5,758.89	61,988.13
13	11th Floor	5,758.89	61,988.13
14	12th Floor	3,137.17	33,768.23
15	13th Floor	2,790.78	30,039.71
16	14th Floor	905.00	9,741.33
17	Roof	-	-
	TOTAL	**103,027.10**	**1,108,973.40**

ACCESIBLE PARKING DISTRIBUTION

LEVEL	NO.
Basement/Podium 1	1-3 per Lobby as per calculations
Ground Floor	1 per Lobby, 1 in Retail zone, 1 in visitor zone
TOTAL	**24**

BICYCLE PARKING DISTRIBUTION

LEVEL	NO.
Basement/Podium 1	269 RACKS
Ground Floor	84 RACKS
TOTAL	**353**

GARBAGE CALCULATION

USAGE	REQUIRED	PROPOSED
Residential Area	31	31
Retail Area	1	1
TOTAL	**32**	**32**

LIFT CALCULATION

USAGE	REQUIRED	PROPOSED
Passenger Lift	9	9
Service Lift/Fireman's Lift	8 (Multipurpose/ SE/PE/FL)	8(Multipurpose/ SE/PE/FL)
Waste Transfer Lift	1	1
External Lift	1	1
TOTAL	**19**	**19**

188 sqm Leasable store in GF, 12 sqm in B